SolarStrap™
Patented

Installation Guide



www.solarstrap.com

SSIM Rev.042326

SolarStrap™ Installation Manual
Copyright© 2026 by SolarStrap™. All rights reserved.

www.solarstrap.com

The SolarStrap™ is made in the U.S.A. with quality assurance. The unique features of this product and design are patented and copying of intellectual property without its written consent is prohibited and subject to strict enforcement.

The information contained herein is subject to change without notice.

Designed, and manufactured by:

SolarStrap™ Patented
2750 Garfield Ave
Commerce CA 90040
909-235-6433
www.SolarStrap.com

Rowan Williams Davies & Irwin Inc.
Wind Tunnel Tested per ASCE Standard 7 and ASCE 49
Report Number 1803163

Intertek
Intertek ETL

UL1703 20150519 §48.1.b)1): The system achieves a Class A fire rating when installed in the manner specified in these instructions.
UL2703 First Edition 20150128 §26.1: The system has achieved a Class A fire rating when installed with Type 1, Type 2, Type 3, and Type 29 modules.

ul.com
File No. E356152
UL467 Report: QIMS2.E356152
UL467 Intertek Report: 101005952LAX-001
UL1703: Class A Pending or currently exempt as a roof mount only system (subject to module fire class rating)
UL2703 Certificate of Compliance: 20140820 – E356152

International Code Council Evaluation Services
ICCESR-3839 SolarStrap™ Attachment System
www.icc-es.org

City of Los Angeles Research Report
LA RR 26108
www.ladbs.org

CAUTION

Installer must read this manual before attempting installation. Failure to correctly establish the requirements of the proposed installation site is dangerous and can void the framing or roofing warranty. Please contact Casey Smith at 909-235-6433 or at info@solarstrap.com to verify latest revision of this manual

Copyright© 2026 by SolarStrap. All rights reserved

Table of Contents

Before You Start

- Handling & Installing 4
- Roof Loading Resistance, and Seismic Attachments 4
- Features 4

System Overview

- Diagram 5
- Components 5

Preparing to Build

- Required Tools and Safety Equipment 6

Planning and Layout

- Setting Up the Roof 7
- Roof Layout 8
- Laydown Straps 8

Installation

- Add Brackets 9
- Place Modules 10
- Clamp Installation 11
- Wire Management and Grounding 12
- Grounding the Array Example 13

Seismic Engineering

- Application of Seismic Building Codes 14

Roof Connection

- Attachment Details for Built-up or Asphalt Roofs 15
- Attachment Details for TPO or PVC Roofs 16
- Attachment Detail for Premium TPO or PVC Roofs 17

Notes

- Parts List 18

Certifications and Approved Modules

- ETL UL2703 - Conformance 19
- ETL UL2703 - Approved Modules 19

Warranty

- SolarStrap™ Limited Warranty Statement 20

Revision History

- Log of changes to install manual 21

Warranty Check List

- Warranty check list 22

UL 3741 Addendum

- UL3741 Purpose/Introduction 23
- PVHCS Listed Components 24
- Installation Array Case 1 28
- Installation Array Case 2 29
- Installation Array Case 3 30
- Installation Array Case 4 31
- UL 3741 Wire Management 32

Copyright© 2026 by SolarStrap. All rights reserved

BEFORE YOU START

Handling & Installing

It is critically important to observe standard safety practices when installing SolarStrap™:

- Follow all OSHA safety guidelines for construction safety.
- Stop work during stormy weather. Solar modules, SolarStrap, and other components can be blown off the roof in high winds.
- Always secure solar modules, SolarStrap, and other components from unexpected high winds while under construction. Windblown construction materials are a safety hazard.
- Never step or sit on the glass surface of a solar module. The glass may break, resulting in shock or bodily injury.
- Do not throw or roughly handle any SolarStrap™ components.
- Do not bring SolarStrap™ into contact with sharp or heavy objects.
- Do not modify SolarStrap™ components in any way. The exchange of bolts, drilling of holes, bending and any other physical changes not intended in standard installation procedure will void the warranty.
- Products should be installed and maintained by qualified personnel. Keep unauthorized personnel away from solar modules.
- It is the installer's responsibility to verify the integrity of the structure to which SolarStrap™ is used. Roofs or structures with rotten/rusted bearers, undersized bearers, excessively spaced bearers or any other unsuitable substructure cannot be used with SolarStrap™. Installation on such structures could result in death or serious injury.
- Installation is to be periodically re-inspected for loose components, loose fasteners and any corrosion. Any affected components are to be immediately replaced.

Roof Loading Resistance, and Seismic Attachments

Roof loading calculation are based on code approved stress equations and allowable margins of safety. Roof loading calculations must be conservatively performed under wind loads, snow, and dead loads. Components have had full envelope forces applied to each component from engineered data sets approved by the Engineer of Record (EOR). The EOR will review SolarStrap™ wind data tables and choose the appropriate wind uplift values by boundary roof zones. The EOR will choose and compute the quantity and method of positive seismic attachments required based on roof type, roof substructure and seismic locations. This data is either provided as part of the project engineering or from a SolarStrap code compliant dataset.

Features

- Aluminum 5052 - 6061
- Suitable for most buildings
- Suitable for roof slope range 0°<9.5°
- Panel array weight under (3) PSF
- High strength-to-weight ratio
- Spacing efficiency with integrated setback adjustments
- High corrosion resistant materials resulting in low lifetime maintenance and an extended product life
- Complies with ASCE 7-05, 7-10, and 7-16 guidance for design criteria
- Complies with SEAOC PV-1 for seismic designs
- Complies with SEAOC PV-2 guidance for wind tunnel tested arrays
- Wind tunnel tested by RWDI
- Peer reviewed by CPP

Copyright© 2026 by SolarStrap. All rights reserved

SYSTEM OVERVIEW

Diagram

The SolarStrap™ is fast and easy to install with minor field measurements required.
The PanStrap option is available when used in conjunction with SolarStraps's wind tunnel test data in compliance with SEAOC PV-2 Guidelines.

Note: The SSSS4 or SSOP3 will need to be in every installation for that installation to retain Fire Rating. (UL2703 First Edition 20150128 §26.1)
Note: Marking plate will be stamped into each SSOP3 near the middle of the part, see location shown below under components.



Components

SolarStrap™ One Piece w/UL Marking Stamp
SSOP3

SolarStrap™ Low Bracket
(0°,5°, 10°, 15°) SSLB

SolarStrap™ High Bracket (5°, 10°, 15°)
SSHB

SolarStrap Pan Strap

SSPS3

SolarStrap™ Bonding Bar

SSBB

Conductive Mid Clamp*
A3004

Conductive End Clamp*
A3003

Grounding Lug*
SGB-4

Grounding Lug*
SGB-5

Serrated Hex Flange Nut
SSHWSFN

Conductive Mid Cap*
500100

Conductive End Cap Universal*
500101

Full Threaded Hex Bolt
SSHWHB

Lock Washer
SSHWLW

SolarStrap™ Attachment Plate SSAP

SolarStrap™ Inverter Mount
SSIMR**

SolarStrap™ Single Ply Continuous Cap 10" x 100'
SSCC

SolarStrap™ Single Ply Cap 11.5" CIRCLE
SSPC

SolarStrap™ Single Ply Tie

SSPTD

* Note: For certain jurisdictions these items may be single use only. Please check with local AHJ for more information regarding single use bonding
**Not evaluated under UL listing

Copyright© 2026 by SolarStrap. All rights reserved

PREPARING TO BUILD

Required Tools and Safety Equipment

Chalk Line Reel

7/16” Socket

Measuring Tape

Torque Wrench

Footwear

Gloves

Hard Hat

Safety Glasses

Safety Harness

Safety Vest

Copyright© 2026 by SolarStrap. All rights reserved

PLANNING AND LAYOUT

Setting Up the Roof

Utilizing a grid style pattern, layout arrays on the roof



- X= Module length + 3/4" (.75")
  - Center to Center of straps
  - For frameless modules please refer to plan set
- Y^1= Varies depending on tilt angle
  - From front attachment to second attachment
    - 5° tilt = 38.75"
    - 10° tilt = 43.5"
    - 15° tilt = 45.5"
- Y^2= Varies depending on project see plan set for exact measurements
  - From second attachment repeating till end of array
- Modules are mounted in Landscape orientation
- Snap and Detail horizontal and vertical lines to identify locations of all attachments



⚠ CAUTION

- AHJ may request seismic attachment for certain zones. Verify with your local department of building and safety.
- Be careful to follow final design layout.
- Installer must verify that PV Module manufacturer's attachment points for clamps are met to avoid damage, injuries and module warranty being voided.
- Installers must verify that all building requirements specific to installation site are met, including city, fire department, and other jurisdictions responsible for Residential/Commercial roof inspections.
- Installer must follow all OSHA CFR1926 rules and regulations regarding Job-site safety, fall protection and PPE. For more info visit: www.osha.gov

Copyright© 2026 by SolarStrap. All rights reserved

PLANNING AND LAYOUT

Roof Layout

Utilizing approved plan set locate and install proper attachments on chalk grid pattern.
NOTE: Before making any penetrations into roof, verify warranty information! If you have any question on warranty, contact SolarStrap at info@solarstrap.com or 909-235-6433



Laydown Straps

After proper attachment points are installed per approve plan set, simply layout SolarStraps on top of attachment points. Once straps are in place properly secure the attachment utilizing approved details on plan set.

NOTE:
ONCE THE CORRECT INTERLOCK SETTING HAS BEEN ESTABLISHED BY SOLARSTRAP AND/OR APPROVED PLANS BY AHJ/BUILDING DEPARTMENT.INTERLOCK ALL SSOP3 - SOLARSTRAP TO THE ESTABLISHED SETTING. THIS WILL MAKE THE INSTALLATION AND MOUNTING OF SOLARSTRAP COMPONENTS AND SOLAR EQUIPMENT FAST AND EASY.



⚠ CAUTION

- Before performing any roof work a test fit must be accomplished by setting up a minimum of a 2 module by 2 module array and ensuring all attachments align with straps. Please call SolarStrap at 909-235-6433 and speak with technical support for help!

Copyright© 2026 by SolarStrap. All rights reserved

INSTALLATION

Add Brackets

After SolarStraps™ are laid down, simply place brackets over the integrated pem studs on the SolarStraps with top flanges facing inwards. The low bracket is for the sun-facing side and the high bracket for the shade-facing side. Fasten with Serrated Hex Flange Nuts to secure brackets, torque of **84 in.-lbs**.

Copyright© 2026 by SolarStrap. All rights reserved

Place Modules

After brackets are secured, simply place modules on brackets. Install mid and end clamps and torque to 84 in.-lbs. or manufactures recommendation. Take special care to ensure modules are centered on brackets.

Note: For Sunpreme module torque to manufactures recommendations.



NOTE: Ensure the use of supplied split lock washer on mid clamp and end clamp bolts. (see pg. 11) According to some AHJ clamps are considered single-use items, if you need to remove clamp it must be replaced with a new clamp. Please contact SolarStrap to acquire replacement hardware.

SolarStrap must be secured to the modules by using the supplied “Conductive Mid-Clamps and End-Clamps" (for framed modules) or the “Frameless End Clamps” for the frameless modules, such as Sunpreme.

⚠ CAUTION

Never leave unsecured modules on the roof unattended.

Copyright© 2026 by SolarStrap. All rights reserved

CLAMP INSTALLATION

NOTE: Directions apply to all clamps sold by SolarStrap

Mid Clamp with Integrated Ground Installation

Install mid clamp utilizing supplies bolts and split lock washers. Take special care to ensure modules are centered on brackets.

Torque: Conductive Mid Clamp A3004 = 84i in. lbs.

Conductive Mid Cap 500100 = 84 in. lbs.



End Clamp with Integrated Ground Installation

Install End clamp utilizing supplies bolts and split lock washers. Take special care to ensure modules are centered on brackets

Torque: Conductive End Clamp A3003 = 84 in. lbs

Conductive end Cap Universal 500101 = 84 in. lbs.



Note: For frameless modules, use Module Manufactures installation manual for torque spec.

Frameless Module setup



⚠ CAUTION

Over torquing could result in module damage and voiding of warranty. Never torque more than 84 in.-lbs. Clamps must be in proper location with the bolt center at the least 2.5" from the frame edge.

Copyright© 2026 by SolarStrap. All rights reserved

INSTALLATION

Wire Management and Grounding

The SolarStrap™ is certified by UL2703 to be used for integrated grounding in two directions. (1) primary from module to module bonded by the Conductive Mid Clamp and (2) Through the SolarStrap connected to Mid Clamp or End Clamp. For frameless modules the SolarStrap Bond Bar (SSBB) is used to connect SolarStraps together to maintain a continuous bond. The Maximum number of adjacent bonded PV modules or Straps from the "Grounding Lug" (SGB-4 or SGB-5) attached to the first supporting bracket is limited by the inverter DC ground conductor size or 360 modules, no more than 40 modules across from the SolarStrap connected to the grounding lug. For installations where some of the modules cannot be installed adjacent to each other the following methods may apply.

a. A bare solid #6 AWG copper conductor or A #6 AWG stranded with XHHW-2 90°c insulation with a maximum length of 30 feet bonded using approved grounding lug (SGB-4 or SGB-5)
b. Use of SSBB to bond gaps; including walkways
c. The use of SSBB to bond frameless modules straps together is required since bonding not available through a module frame



NOTE:
Utilize pem studs and supplied serrated flange nuts to secure SSBB

⚠ CAUTION

Employ best industry practices to ensure copper does not contact aluminum or galvanized steel.

Simply attach ground wire to the provided Grounding Lug (SGB-4 or SGB-5) fastened to the wing of the low or high bracket and connect the ground wire to the pull box that is mounted on the back of the high bracket. From the pull box run ground wire all the way to the inverter or combiner box per the electrical engineering drawing.

PVC Schedule 80, EMT, IMT, or Rigid conduit may be secured to any part of the brackets and should be six inches or more above the roof to minimize heat gain and wire heat losses. Conduit may pass under the array to take the most direct path to inverters or combiner boxes. For wire management use EMT or Schedule 80 PVC conduit supported by a one-hole strap and one self-tapping screw to attach your conduit to the side of the wing. Use plastic end protection if using EMT. EMT should be avoided for inter row crossings if the local AHJ requires bonding of EMT at these locations.

Note: A SSBB is only required on frameless modules, to bond the rows to columns. One per bonded 40 modules.
Note: This racking system may be used to ground and/or mount a PV module complying with UL 1703 only when the specific module has been evaluated for grounding and/or mounting in compliance with the included instructions.

Copyright© 2026 by SolarStrap. All rights reserved

INSTALLATION

Grounding the Array Example

Up to 360 modules in an array requires one grounding lug (SGB-4 or SGB-5/Torque to 55 in. lbs) secured to one bracket. A bare #6 AWG solid copper or stranded wire with XHHW-2 90°c insulation may be used to bond each grounding lug (SGB-4 or SGB-5/Torques to 55 in. lbs) to the Earth Ground. The grounding lug must be placed on a continuous strap. Stranded rows of modules may ground through straps to the adjoining row. For islands of modules a bare #6 AWG solid copper or stranded wire with XHHW-2 90°c insulation jumper ground wire connects islands of modules together through grounding lugs (SGB-4 or SGB-5/Torque to 55 in. lbs) secured to one bracket per section. A SolarStrap™ Bond Bar (SSBB) can also be used to connect islands of modules. All bonding/grounding hardware is to be used in accordance with the National Electric code, ANSI/NFPA70



Copyright© 2026 by SolarStrap. All rights reserved

SEISMIC ENGINEERING

Application of Seismic Building Codes

SolarStrap™ is uniquely suited for installation of rooftop mounted PV solar systems in seismically active areas and on buildings with limited roof structural capacity. Due to its light weight and flexible mounting options, the SolarStrap™ is a viable option for a wide range of rooftops. Our design allows the SolarStrap™ to be mounted to the roof using one of three mounting options: structurally attached; ballasted; and a hybrid option that uses both ballasted and structural attachments. Calculations have been performed in accordance with the 2013 California Building Code (CBC), the governing building code in California, which references the 2012 International Building Code (IBC). The 2012 IBC references the 2010 Minimum Design Loads for Buildings and Other Structures, including Supplement No. 1, No. 2, and Errata, by the American Society of Civil Engineers (ASCE), referred to as ASCE 7-10. The anchorage designs have been designed to withstand code-prescribed seismic forces due to the self-weight of the racking system, the self-weight of the solar panels and the system's ballast, if present.

Our structural analysis and design of the SolarStrap™ and its method of attachment (ballasted, structurally attached and the hybrid ballasted with structural attachment) complies with Section 13.4 of ASCE 7-10, which states that all components shall be positively fastened to the structure without consideration of frictional resistance. The intent of our design is to provide a solution for various design parameters for seismic anchorage in a variety of site-specific conditions. Since there are many different possible seismic conditions, we can provide a site-specific seismic anchorage configuration with calculations to assure a safe installation and to obtain building permits. The seismic forces used in our calculations assume Site Class D and utilize short- period spectral accelerations as provided in ASCE 7-10. The design parameters may also be customized by roof material type.

Limitations

For certain projects, site-specific engineering may be recommended to help determine a very efficient custom installation cost. These various building-specific issues must be evaluated by the appropriate registered professional(s) prior to the addition of the photovoltaic and racking systems. A licensed structural engineer shall be consulted for building-specific structural evaluation.

Copyright© 2026 by SolarStrap. All rights reserved

ROOF CONNECTION

Basic Attachment Details for Built-up or Asphalt Roofs

NOTE: See approved plan set for site specific attachment details.



Note: EOR required to review suggested site plans. EOR shall review/recommend proper roof attachments that are commercially available

Copyright© 2026 by SolarStrap. All rights reserved

ROOF CONNECTION

Basic Attachment Details for TPO/PVC Roofs

NOTE: See approved plan set for site specific attachment details.

`



Note: EOR required to review suggested site plans. EOR shall review/recommend proper roof attachments that are commercially available

Copyright© 2026 by SolarStrap. All rights reserved

ROOF CONNECTION

Basic Attachment Details for Premium TPO/PVC Roofs

NOTE: See approved plan set for site specific attachment details.



Note: EOR required to review suggested site plans. EOR shall review/recommend proper roof attachments that are commercially available

Copyright© 2026 by SolarStrap. All rights reserved

NOTES

Parts List

Product	Product Number	Quantity	Note
SolarStrap™ One Piece	SSOP3		
SolarStrap™ Bond Bar	SSBB		
SolarStrap™ Pan Strap	SSPS		
SolarStrap™ Inverter Mount Rack	SSIMR		
SolarStrap™ Attachment Plate	SSAP		
SolarStrap™ High Bracket 5˚/10˚/15˚	SSHB		
SolarStrap™ Double High Bracket 5˚/10˚/15˚	SSHBEW		
SolarStrap™ Low Bracket 5˚/10˚/15˚	SSLB		
SolarStrap™ Double Low Bracket 5˚/10˚/15˚	SSLBEW		
Conductive Mid Clamp	A3004		
Conductive End Clamp	A3003		
Conductive Mid Cap	500100		
Conductive End Cap Universal	500101		
Grounding Lug	SGB-4		
Serrated Hex Flange Nut	SSHWSFN		
Single Ply Continuous Cap	SSCC		
Single Ply Tie	SSPT		
Single Ply Cap	SSPC		

Copyright© 2026 by SolarStrap. All rights reserved

UL CERTIFICATIONS AND APPROVED MODULES

ETL UL2703 - Conformance

Fire Conformance
Intertek Reference File
105405473lax-001

Mechanical Conformance
Intertek Reference File
105405473lax-001

Electrical Conformance
Intertek Reference File
105405473lax-001

ETL UL2703 - Approved Modules

Boviet
- BVM6610P-XXX
- BVM6610M-XXX
- BVM6612M-XXX
- BVM6612P-XXX

Canadian Solar
- CS3U-XX-XXX
- CS3K-XX-XXX
- CS6U-XXXP
- CS6U-XXXM
- CS6U-XXXP(1500V)
- CS6U-XXXM (1500V)

ecoSolargy
- ECOXXXH156P-72

Hansol
- HSXXXTD-AN4

Hanwha Q Cells
- Q.PLUS L-G4.2 XXX
- Q.PEAK L-G4.2 XXX
- P.PLUS L-G4.1 XXX
- Q.PLUS L-G4 XXX
- Q.PRO L-G4 XXX
- Q.PRO L-G4.1 XXX
- Q.PRO L-G4.2 XXX
- B.LINE PLUS L-G4.2 XXX
- B.LINE PRO L-G4.1 XXX
- B.LINE PRO L-G4.2 XXX
- Q.PEAK DUO L-G8.3/BFG/BGT XXX
- Q.PEAK DUO XL-G9.3/BFG XXX

HT Solar
- HT72-156M(V)-C

Hyundai Heavy Industries
- MI-Series
- Hix-xxxHI

LG
- LG 280W
- LGXXXN2T-A5
- LGXXXN2W-A5
- LGXXXN1C-V5
- LGXXXN1K-A5
- LGXXX1C-A5
- LGXXXS2W-A5
- LGXXXS2W-G4
- LGXXXN2T-J5

Neo Solar Power Corporation
- D6MXXXE4A
- D6MXXXB4A
- D6MXXXE4AME

Panasonic
- VBHNXXXSA17
- VBHNXXXSA17G
- VBHNXXXSA17E
- VBHNXXXSA18E
- VBHNXXXSA18
- VBHNXXXSA15
- VBHNXXXSA16

Phono Solar
- PSXXXmXFG

Risen
- Rsm144-6-xxx

SunPower
- X-Series
- SPRxxxNE
- P Series
- SPR-PXX-XXX-COM

Solar World
- Sunmodule Pluse
- SW XXX Mono

Sunpreme
- Maxima GxB 360WB

Trina Solar
- TSM-PE14A
- TSM-DE15H(II)
- TSM-PD14
- TSM-DE14A(II) STD MONO
- TST-PE15H
- TSM-DE14A(II) PERC MONO

VSUN
- VSUN60X-XX
- VSUN72X-XX
- VSUN120X-XX
- VSUN144X-XX

ZNShine
- ZXM7-NH144-XXX/M182
- ZXM7-NHLDD144-XXX/M182
- ZXM6-NH144-XXX/M166
- ZXM6-NHLDD144-XXX/M166

NOTE: Consult site-specific installation drawings for system load ratings

SolarStrap™ Limited Warranty Statement

Copyright© 2026 by SolarStrap. All rights reserved

Warranty

NOTE: CHECK LIST ON PG 22 MUST BE COMPLETE AND RETAINED ON SITE AS WELL RETURN A COPY TO SOLARSTRAP. INFO@SOLARSTRAP.COM

Product	Product Number	Duration of Limited Warranty
SolarStrap™ One Piece/Gen3	SSOP3/Gen3	25 Years
SolarStrap™ Attachment Plate	SSAP	25 Years
SolarStrap™ Pan Strap	SSPS	25 Years
SolarStrap™ Double High Bracket (5˚, 10˚, 15˚)	SSHBEW	25 Years
SolarStrap™ Low Bracket (5˚, 10˚, 15˚)	SSLB	25 Years
SolarStrap™ Double Low Bracket (5˚, 10˚, 15˚)	SSLBEW	25 Years
Conductive Mid Clamp	A3004	25 Years
Conductive End Clamp	A3003	25 Years
Conductive End Cap Universal	500101	25 Years
Conductive Mid Cap	500100	25 Years

A. Extent of Limited Warranty
   1. SolarStrap warrants to the end-user customer that the SolarStrap products specified above will be free from defects in materials and workmanship for the duration specified above, which duration begins on the date of purchase by the customer.
   2. SolarStraps's limited warranty covers only those defects that arise as a result of normal use of the product, and does not cover any other problems, including those that arise as a result of:
      a. Improper maintenance or modification;
      b. Parts or supplies not provided or supported by SolarStrap;
      c. Operation outside the design specifications or engineering;
      d. Unauthorized modification or misuse.
   3. If SolarStrap receives, during the applicable warranty period, notice of a defect in any product which is covered by SolarStrap's warranty, SolarStrap shall either repair or replace the product, at SolarStrap's option.
   4. If SolarStrap is unable to repair or replace, as applicable, a defective product which is covered by SolarStrap's warranty, SolarStrap shall, within a reasonable time after being notified of the defect, refund the purchase price for the product.
   5. SolarStrap shall have no obligation to repair, replace, or refund until the customer returns the defective product to SolarStrap.
   6. Any replacement product may be either new or like-new, provided that it has functionality at least equal to that of the product being replaced.
   7. SolarStrap products may contain remanufactured parts, components, or materials equivalent to new in performance.
   8. SolarStrap's Limited Warranty Statement is valid in any country where the covered SolarStrap product is distributed by SolarStrap. Contracts for additional warranty services, such as on-site service, may be available from any authorized SolarStrap service company in countries where the product is distributed by SolarStrap or by an authorized importer.

B. Limitations of Warranty
   To the extent allowed by local law, neither SolarStrap nor its third-party suppliers make any other warranty or condition of any kind, whether express or implied warranties or conditions of merchantability, satisfactory quality, and fitness for a particular purpose.

C. Limitations of Liability
   1. To the extent allowed by local law, the remedies provided in this Warranty Statement are the customer's sole and exclusive remedies.
   2. To the extent allowed by local law, except for the obligations specifically set forth in this warranty statement, in no event shall SolarStrap or its third party suppliers be liable for direct, indirect, special, incidental, or consequential damages, whether based on contract, tort, or any other legal theory and whether advised of the possibility of such damages.

   D. Projects located within 2.5 miles of the ocean must use marine grade option, using either coated stainless steel serrated hex flange nut, pem studs, and pem nuts or these items made in aluminum.

The only warranties for SolarStrap products and services are set forth in the express warranty statements accompanying such products and services. Nothing herein should be construed as constituting an additional warranty. SolarStrap shall not be liable for technical or editorial errors or omissions contained herein. In order to keep full warranty, please design and build per installation manual guidelines.

SolarStrap™ Installation Manual Copyright© 2025 by SolarStrap. All rights reserved www.solarstrap.com

Copyright© 2026 by SolarStrap. All rights reserved

Revision History

Log of changes to install manual

Revision Number	Date	Description of Change
SSIM REV 070717	07/07/2017	First Draft
SSIM REV 091917	09/19/2017	Submittal to TUV for Certification
SSIM REV 012018	01/20/2018	Updated per TUV review comments
SSIM REV 012318	01/23/2018	Updated per TUV review comments
SSIM REV 012418	01/24/2018	Updated per TUV review comments
SSIM REV 013018	01/30/2018	Minor Format changes/Added Hansol HSXXXTD to approved list
SSIM REV 030118	03/01/2018	Clarify SSTFEC installation.
SSIM REV 011520	01/15/20	Updated to SolarPTL Certs, Added Modules to list, Clarified Installation directions, Updated warranty to 25 years.
SSIM REV 091920	09/19/20	Added FUI 2020 requirement, revert to SSPC from SSCC, Updated approved module list
SSIM REV 012921	02/15/2021	Added new mid and end clamps, Approved modules PTL updates.
SSIM REV 082622	08/26/2022	Updated approved module list, updated layout measurements
SSIM REV 100223	10/02/2023	Removed GEN3, SSSP, Connecting strap for ETL preliminary transfer
SSIM REV 111323	11/13/2023	Added pan strap back into manual
SSIM REV 053024	05/30/2024	Added UL3741 Addendum
SSIM REV 072424	07/24/2024	Simplified UL3741 list, added wire management requirements
SSIM REV 100225	10/02/2025	UL3741 listing updates
SSIM REV 042326	04/23/26	ADDED TYPE 29 TO FIRE LISTING

Copyright© 2026 by SolarStrap. All rights reserved

Warranty Check List

Warranty check list

Part	Required	Actual
¼-20 Module Clamp bolt torque	84 in-lb Torque	
¼-20 Hex Flange Nuts for brackets	84 in-lb Torque	
Tie Heat Welds if required	2in each side	
Cap Heat Welds if required	Fully welded	
¼-20 Hex Flange nuts for ties	Snug	
5/16-18 Hex Flange Nuts if required	84 in-lb Torque	
SolarPTL Stamp on straps	Each strap	

Project name

Project address

Inspectors printed name

Signature

Date

Check list shall be completed by site foreman representing solar install team.

Copyright© 2026 by SolarStrap. All rights reserved

UL3741 Addendum:

WARNING: To Reduce the Risk of Injury, read all instructions.

Purpose: UL 3741 and NEC 690.12 Introduction

2020/2023 NEC 690.12(B)(2) Controlling Conductors within the array boundary.

- SolarStrap™ Photovoltaic Hazard Control System (PVHCS) is a UL 3741 Listed system that complies with NEC 690.12(B)(2) (1), when installed by qualified persons per the installation procedures outlined in the SolarStrap™ Installation Manual and this Addendum. Please refer to the following pages of this addendum for various example cases of system designs that comply with 690.12(B)(2).
- These installation instructions describe system installation in accordance with NEC (NFPA 70) and Canadian Electrical Code (CE Code, C22.1).
- Rapid Shutdown of PV Systems on Buildings requires that all PV arrays installed on or in buildings shall include rapid shutdown functions to reduce shock hazard for Fire Fighters (FF) in accordance with 690.12(A) through (D):
  - A. Controlled Conductors
    - a. PV System DC Circuits
    - b. Inverter Output Circuits originating from inverters located within array boundary
  - B. Controlled limits
    - a. Outside Array Boundary: ≤30V within 30 seconds
    - b. Inside Array Boundary – The PV System shall comply with one of the following:
      - i. Listed PV Hazard Control System (UL 3741)
      - ii. ≤80V within 30 seconds after rapid shutdown initiation
      - iii. PV array without exposed wiring methods or conductive parts (NEC 2020 only)
  - C. Initiation devices
    - a. Initiation device(s) shall initiate the rapid shutdown function of the PV system
  - D. NEC 2020 - Equipment
    - a. Equipment that performs rapid shutdown functions, other than initiation devices such as listed disconnect switches, circuit breakers, or control switches, shall be listed for providing rapid shutdown protection.
  - E. NEC 2023 - Buildings with Rapid Shutdown
    - a. Buildings with PV systems shall have a permanent label located at each service equipment location to which the PV systems are connected or at an approved readily visible location and shall indicate the location of rapid shutdown initiation devices.

➢ NEC 690.2 (2020) or Article 100 (2023) defines the array as a mechanically and electrically integrated grouping of modules with support structure, including any attached system components such as inverter (s) or dc-to-dc converter(s) and attached associated wiring.

➢ NEC 690.12(B) defines the array boundary as 1ft from array in all directions. This indicates that the array boundary can extend 1ft from the edge of the SolarStrap™ racking, inverter, or module.

➢ The inverter is considered within the array boundary if mechanically attached and within 1 foot of the mounting system or module.

Installation Methods per UL 3741

SolarStrap™ provides the following examples on illustrations that may comply with NEC 690.12(B) to comply with UL3741.

- Case 1: UL 3741 Listed system single array with one or more inverters within 1 foot of array boundary
- Case 2: UL 3741 Listed system, Case 1 Array with one or more Sub-Arrays less than 2 feet away from Case 1 array
- Case 3: UL 3741 Listed system, Case 1 Array with one or more Sub-Arrays MORE than 2 feet away from Case 1 array, utilizing String Isolation devices within 2' of each array
- Case 4: UL 3741 Listed system, Case 1 Array with one or more Sub-Arrays More than 2 feet away from Case 1 array, Utilizing MLPE devices on each sub array.

Testing & Maintenance of the PVHCS

PV Hazard Control System (PVHCS) installations shall be inspected periodically in accordance with NEC 690.12(D).
Inspections shall confirm:

- All wire management remains secured as shown in this manual.
- No components have been substituted with non-listed equipment.
- All bonding jumpers remain intact if modules have been serviced or replaced.

Testing shall include verification of rapid shutdown initiation from the service disconnect or other initiation device.

Copyright© 2026 by SolarStrap. All rights reserved

PVHCS Components

WARNING: Replacement of any PV Hazard Control System (PVHCS) equipment, including modules, inverters, or wire management devices, shall only be performed with identical make and model components listed in this manual. Substitution may void UL 3741 compliance.

String Max System Voltage: 1000Vdc
Max PV Module Surface Area: 30.25 ft2
PV Module Model Type: Type 1 and 2
Max Array Tilt = 10°

INVERTERS

Manufacturer	Model	Manufacturer	Model
Canadian Solar Inc.	CSI-25K-T480GL01-UB	GoodWe Technologies	GW50K_60K-SMT-US
	CSI-30K-T480GL01-UB	SMA Solar Technologies	STP-33-US-41
	CSI-36K-T480GL01-UB		STP-50-US-41
	CSI-40K-T480GL01-UB		STP-62-US-41
	CSI-25KTL-GS-FLB		STP-20-US-50
	CSI-30KTL-GS-FLB		STP-25-US-50
	CSI-36KTL-GS-FLB		STP-30-US-50
	CSI-40KTL-GS-FLB	Solectria Renewables	PVI 25TL-208
	CSI-50K-T480GL01-UB		PVI 25TL-480-R
	CSI-60K-T480GL01-UB		PVI 50TL-480
	CSI-66K-T480GL01-UB		PVI 60TL-480
	CSI-50KTL-GS-FLB		PVI-36TL-480-V2
	CSI-50KTL-GS-B	Ningbo Ginlong Technologies Co (Solis)	Solis-25K-US-SW
	CSI-60KTL-GS-B		Solis-30K-US-SW
	CSI-66KTL-GS-B		Solis-36K-US-SW
	CSI-75K-T480-GL02-U		Solis-40K-US-SW
	CSI-80K-T480-GL02-U		Solis-50K-US-SW
	CSI-90K-T480GL02-U		Solis-50K-US-F-SW
	CSI-100K-T480GL02-U		Solis-60K-US-F-SW
	CSI-75K-T480GL03-U		Solis-66K-US-F-SW
	CSI-80K-T480GL03-U		Solis-75K-5G-US
	CSI-90K-T480GL03-U		Solis-80K-5G-US
	CSI-100K-T480GL03-U		Solis-90K-5G-US
Shanghai Chint Power Systems	CPS-SCA25KTL-DO-US-480		Solis-100K-5G-US
	CPS-SCA25KTL-DO-US-208		Solis-50K-US-SW
	CPS-SCA36KTL-DO-US-480	SunGrow Power Supply	SG36CX-US
	CPS-SCA50KTL-DO-US-480		SG60CX-US
	CPS-SCA60KTL-DO-US-480		
Fronius International	SYMO 15.0-3 480		
	SYMO 20.0-3 480		
	SYMO 22.7-3 480		
	SYMO 24.0-3 480		

Only the inverter modules listed in this section are included in the UL 3741 certification. Subsitution with any other inverter model is not covered by this listing.

Copyright© 2026 by SolarStrap. All rights reserved

WIREWAY & CONDUIT

Name	Manufacturer	Model	Technical Details	Mark(s) of conformity
	RayTray Solar, LLC	RayTray	Max support interval: RayTray 4 feet 3 inches, RayTray V2 4 feet. Approved for outdoor use. Used with wire sizes between 6 AWG and 12 AWG. Wire fill ratio 20%,	ETLus
		RayTray V2		
	Various	Various Conduit	Electrical Metallic Tubing (EMT) with compatible and certified end components (No enclosure or Junction box or similar electrical boxes just Conduit fittings) to protect the wire. Min size: 3/4"	UL
	Various	Various Conduit	Rigid Metal Conduit (RMC)with compatible and certified end components (No enclosure or Junction box or similar electrical boxes just Conduit fittings) to protect the wire. Min size: 3/4"	UL
	Various	Various Conduit	Intermediate Metal Conduit (IMC) with compatible and certified end components (No enclosure or Junction box or similar electrical boxes just Conduit fittings) to protect the wire. Min size: 3/4"	UL
	Various	Various Conduit	Non-metalic aboveground PVC Schedule 40 & 80, with compatible and certified end components (No enclosure or Junction box or similar electrical boxes just Conduit fittings) to protect the wire. Min size: 3/4"	UL
	Various	Various Conduit	Flexible Metal Conduit "3/4 inch and greater	UL
Clamp Tie	HellermannTyton	CTT60R0HSC2	Heat stabilized cable ties Clamp Tie, 8" Long, 60lb Tensile Strength, PA66HS, Black, 100/pkg, Placed around wires and into holes on modules to ensure wires stay under modules and not exposed	UL
Cable Tie	HellermannTyton	T50R-PA66HS-BK	Heat stabilized cable ties Clamp Tie, 8" Long, 60lb Tensile Strength, PA66HS, Black, 100/pkg, Placed around wires and into holes on modules to ensure wires stay under modules and not exposed	UL
Heyclip Stainless Steel SunRunner 1-2	HeyCo	S6405	HeyClip SunRunner Cable Clips robust "double-compression" design securely holds from (1) 12 gauge USE-2 to (2) 10 gauge PV-1000V solar wires. SunRunner Clips are designed to provide a better method for PV module wire management and may be used wherever single or multiple cable management is needed. 100 per pack	UL
Heyclip Stainless Steel SunRunner 1-2	HeyCo	S6455	HeyClip SunRunner Cable Clips robust "double-compression" design securely holds from (1) 12 gauge USE-2 to (2) 10 gauge PV-1000V solar wires. SunRunner Clips are designed to provide a better method for PV module wire management and may be used wherever single or multiple cable management is needed. Bulk pack	UL
Heyclip Stainless Steel SunRunner 4-2	HeyCo	S6505	HEYClip Stainless Steel SunRunner 4-2 Designed to hold Micro-Inverter oval cables, Constructed from heat treated 410 stainless steel for excellent strength and corrosion protection for outdoor exposure 100 per pack	UL
Heyclip Stainless Steel SunRunner 4-2	HeyCo	S6545	HEYClip Stainless Steel SunRunner 4-2 Designed to hold Micro-Inverter oval cables, Constructed from heat treated 410 stainless steel for excellent strength and corrosion protection for outdoor exposure bulk pack	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6484	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard	UL

Copyright© 2026 by SolarStrap. All rights reserved

			pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 4" Length	
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6486	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 6" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6408	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 8" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6410,	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 10" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6412	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 12" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6414	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 14" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6420	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 20" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6424	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 24" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6426	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 28" Length	UL

Copyright© 2026 by SolarStrap. All rights reserved

Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6428	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 32" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6430	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 36" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6491	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 40" Length	UL
Heavy Duty Stainless Steel Wire Cable Ties	HeyCo	S6493	Heyco Heavy Duty Stainless Steel Wire cable ties Smooth vinyl jacketing prevents damage to installation cable insulation, Easy field installation using standard pliers or wire cutters to both crimp the sleeve and cut the excess wire Placed around wires and into holes on modules to keep wires protected and under the module. 44" Length	UL
Clamp Steel	Eaton	200	Clamps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets 1/2" Conduit	UL
Clamp Steel	Eaton	201	Clamps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 3/4" Conduit	UL
Clamp Steel	Eaton	202	Clamps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets For 1" Conduit	UL
Clamp Steel	Eaton	203	Clamps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets For 1-1/14" Conduit	UL
Clamp Steel	Eaton	204	Clamps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 1-1/2" Conduit	UL
Clamp Steel	Eaton	205,	Clamps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 2" Conduit	UL
Straps Steel	Eaton	497 1,	Straps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 1/2" Conduit	UL
Straps Steel	Eaton	497 2	Straps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 3/4" Conduit	UL
Straps Steel	Eaton	497 3	Straps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 1" Conduit	UL
Straps Steel	Eaton	497 4	Straps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 1-1/4" Conduit	UL
Straps Steel	Eaton	497 5	Straps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 1-1/2" Conduit	UL
Straps Steel	Eaton	497 6	Straps to support conduit runs, mounted to SolarStrap Highbracket and lowBrackets for 2" Conduit	UL

NOTE: Array setbacks vary by Area Having Jurisdiction, (AHJ) Please check with local AHJ for minimum set back requirements.

Copyright© 2026 by SolarStrap. All rights reserved

UL3741 Case 1 Array(s)

Array(s) comply with NEC 690.12(B)(2)(1)

PV Circuit Voltages:

Outside array boundary:
≤30V within 30 Seconds

Inside Array Boundary:
≤1000V

- Case 1 arrays comply with NEC 690.12(B) by utilizing a UL 3741 listed PV Hazard Control System
- All inverter input circuits are contained within the PV array boundary and do not require additional measures to reduce string voltages per NEC 690.12(B)(2)(1) after initiation. (Inverter DC Disconnect, AC breaker or AC disconnect)
- Inverter output circuits are outside of the array boundary and meet the NEC 690.12(B)(1) requirement after initiation. (AC breaker or AC Disconnect)

***Note**:*
Illustrative example only. This case study was not evaluated as part of the UL3741 evaluation.





NOTE: Array boundary extends up to 1 foot from edge of module or edge of SolarStrap racking

NOTE: Array setbacks vary by Area Having Jurisdiction, (AHJ) Please check with local AHJ for minimum set back requirements.

Copyright© 2026 by SolarStrap. All rights reserved

Array (s) comply with NEC 690.12(B)(2)(1)

DC conductors inside Array Boundary

Inverter(s)

AC output conductors outside Array Boundary

PV Circuit Voltages:

Outside array boundary:
≤30V within 30 Seconds

Inside Array Boundary:
≤1000V

- Case 2 arrays comply with NEC 690.12 by utilizing a UL 3741 listed PV Hazard Control System
- All Case 1 array requirements must be met
- All Sub-Arrays must have a maximum of 2 feet spacing, thus resulting in a single array.



***Note**:*
Illustrative example only. This case study was not evaluated as part of the UL3741 evaluation.

Copyright© 2026 by SolarStrap. All rights reserved

UL3741 Case 3 Array(s)

Array(s) comply with NEC 690.12(B)(2)(1)

PV Circuit Voltages:

Outside array boundary:
≤30V within 30 Seconds

Inside Array Boundary:
≤1000V

- Case 3 arrays comply with NEC 690.12 by utilizing a UL 3741 listed PV Hazard Control System **with** NEC Compliant String Isolation Devices when Sub-Array is greater than 2 feet away.

Complete string must be connected to a single isolation device. If used for a partial string, isolation devices required on both sides of the pathway.



***Note**:*
Illustrative example only. This case study was not evaluated as part of the UL3741 evaluation.

NOTE: Array setbacks vary by Area Having Jurisdiction, (AHJ) Please check with local AHJ for minimum set back requirements.

Copyright© 2026 by SolarStrap. All rights reserved

UL3741 Case 4 Array(s) Utilizing MLPE

Array(s) comply with NEC 690.12(B)(2)(1)

PV Circuit Voltages:

Outside array boundary:
≤30V within 30 Seconds

Inside Array Boundary:
≤1000V

Sub-Array Boundary:
≤80V within 30 seconds

- Case 4 arrays comply with NEC 690.12 by utilizing a UL 3741 listed PV Hazard Control System **with** NEC Compliant Module Level Power Electronics on Sub-Array

Main array follows Case 1 array while Sub-Array utilizes listed MLPE devices to isolate.

NOTE: Installer must verify MLEP devices and Inverters meet UL1741 requirement for Rapid Shutdown.



***Note**:*
Illustrative example only. This case study was not evaluated as part of the UL3741 evaluation.

NOTE: Array setbacks vary by Area Having Jurisdiction, (AHJ) Please check with local AHJ for minimum set back requirements.

Copyright© 2026 by SolarStrap. All rights reserved

UL3741 Wire Management Guidelines

- All wire management components noted in the list of approved PVHCS equipment were evaluated and approved.
- All Wires shall be routed in a way to reduce or eliminate potential Fire Fighter interactions.
- All Wires shall be mounted to underside of module frame or along SolarStrap racking.
- Refer to the datasheet and instructions for all the wire positioning device and this manual for proper installation
  - PV Connectors (UL 6703 Listed) shall be compatible and approved for the application
  - PV Wire (UL 4703 Listed)
  - RayTray v2 Solar Wire Management System (UL 870 Listed)
  - Listed Conduit
  - *Electrical Metallic Tubing (EMT) (UL 797 Listed)
  - *Rigid Metal Conduit (RMC) (UL 6 Listed)
  - *Intermediate Metal Conduit (IMC) (UL 1242 Listed)
  - *Flexible Metal Conduit (UL 1 Listed)
  - *Liquid Flexible Metal Conduit (UL 360 Listed)
  - *Liquid Tight Flexible Non-Metallic Conduit (UL 1660 Listed)
  - *Schedule 40/80 Rigid PVC Conduit (UL 651 Listed)
  - *Listed Tubing, Fittings and Grounding Components
- Wires shall be supported at a minimum every 24” with approved wire management clips or ties.
- Take caution to ensure wires are not pinched.



Example of utilizing wire clips and cable ties to manage wires along module frames



Example of utilizing approved wire trays to collect wires together in larger runs.

Copyright© 2026 by SolarStrap. All rights reserved

UL3741 Wire Management Guidelines

- If utilizing conduit on interrow Wires must enter conduit beneath the module and conduit must extend a minimum of 6" underneath module
- Conduit must be attached to SolarStrap utilizing approved conduit clamp or strap listed in PVHCS equipment in this manual, utilizing stainless steel hardware appropriate for the hole size in the approved clamp or strap.

Example of utilizing SolarStrap frame to support wire Gap less than 2 feet. Conduit must extend a minimum of 6" under module.

Example of mounting Conduit to SolarStrap

Copyright© 2026 by SolarStrap. All rights reserved